

RESIDENTIAL UNIT - CONSTRUCTION SPECIFICATIONS

Sheet A-101 Foundation and Shell

Standard Foundations: continuous concrete footing, 16in x 8in, 120 LF

Slab on Grade: 4in concrete slab with vapor barrier, 950 SF

Basement Walls: 8in poured concrete foundation wall, 40 LF

Floor Construction: engineered wood I-joist system, 950 SF

Roof Construction: engineered roof truss system, 1100 SF

Exterior Walls: 2x6 wood stud wall with sheathing, 640 SF

Exterior Windows: vinyl double-hung insulated units, 12 EA

Exterior Doors: insulated steel entry door, 3 EA

RESIDENTIAL UNIT - CONSTRUCTION SPECIFICATIONS

Sheet A-102 Interiors and MEP

Roof Coverings: asphalt shingle roofing, 1100 SF

Interior Partitions: 2x4 wood stud wall with drywall, 380 SF

Interior Doors: hollow core wood door, 9 EA

Wall Finishes: painted gypsum wallboard, 1450 SF

Floor Finishes: engineered hardwood flooring, 950 SF

Ceiling Finishes: painted drywall ceiling, 950 SF

Plumbing Fixtures: kitchen and bath fixture package, 2 EA

Electrical Service And Distribution: 200A residential panel, 1 EA